Abstract estimate of quantities for restoring the Jindagere Tank, Registered No. 376 of Gubbi Taluk.

Items of work	Per	Quantity
Earthwork including watering and tamping (earth available to be used to bund)	C. yd.	4,904
Gravel backing behind revetment	"	872
Excavating foundation for revetment and using the same to bund	"	1,205
Rough stone revetment	"	1,607
Turfing	S. yd.	5,784
Grade stones with bed slabs including cutting figures and painting	Each	35
Index stones	"	25
B. M. stones including cutting figures and painting	"	3
Register number stones do	"	11
Gauge stone including. do	"	1
Clearing jungle shrubs, big honge and other trees	L. S. Rs.	
Sluice.		
Earthwork excavation and usinglit to bund	C. yd.	49
Concrete with surki mortar	C. ft.	41
Burnt brick in surki mortar	"	227
Burnt stone slabs with one line dressing	S. ft.	109
Plastering with surki mortar	Sq.	1'63
Cutting orifice and fixing wooden plug with iron rod, lock and key, etc., complete	L. S. Rs.	
Iron pipe 10" dr. including carting, fixing, etc., complete	R. ft.	45
Waste weir.		
Earthwork excavation	C. yd.	1,225
Burnt brick in surki mortar	C. ft.	682
Burnt stone slabs dressed	S. ft.	455
Plastering with surki mortar	Sq.	3'43
Rough stone work	C. yd.	157
Turfing	S. yd.	37

N. G. KRISHNA IYENGAR,
Executive Engineer.

NEW PALACE DIVISION.

Sealed tenders will be received in the office of the Architectural Executive Engineer, New Palace Division, at Nazarbad, in the City of Mysore, on or before Monday the 2nd September 1918, for the supply of Rolled Steel Girders (British or American Make) as per list hereto appended.

The whole quantity as per list is required to be delivered F. O. R., Mysore, before the end of April 1919, for which the rate per cwt. should be quoted.

If, on account of the uncertain conditions of the market for steel goods any difficulty as regards freight or Government restriction is apprehended, the bidders may quote their rate for delivery, subject to their obtaining the necessary freight and Government Permission in regard to which arrangements will be made officially to procure the necessary Priority Certificate, in favour of the firm whose tender will be accepted and for the quantity included in the tender.

List of Rolled Steel Girders required.

No.	Length	Section		
		Depth	Width of flange	Weight per R.ft.
5	34'—0"	24"	7½"	100 lbs.
1	28'—0"	24"	7½"	100 "
14	34'—0"	20"	7½"	89 "
4	34'—0"	18"	7"	75 "
2	28'—0"	18"	7"	75 "
18	26'—0"	16"	6"	62 "
16	16'—0"	16"	6"	63 "
8	24'—0"	15"	5"	42 "
3	18'—0"	12"	5"	32 "
Total ... 71				

S. H. LAKSHMINARASAPPA,
Architectural Executive Engineer,
In charge of New Palace Division, Mysore.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to the Notification dated 27th July 1918, published on page 722 of Part IV of 32nd issue of *Mysore Gazette*, wherein tenders for constructing a combined building for the Sub-Registrar's Office and Bonded Warehouse at Hole-Narsipur.

R. W. SCALDWELL,
Executive Engineer.